

SEALED TENDERS/ QUOTATIONS (WITH MATERIAL & LABOUR) ARE INVITED FOR

1. Installation of 1000 KVA Transformer (Kirloskar) and other related items for transformer like Cable, Panels etc.

2. Upgrading of Electricity load, installation of Cables & panels inside the building premises as per requirement of Montgomery Guru Nanak Public School, Adarsh Nagar, Jalandhar with in 3 working days.

For detail please visit School Website mgnadarshnagar.org and School premises for proper estimates.

Principal

DETAIL OF ITEMS Installation of Transformer & upgrading of Electricity load with cable & panels etc.

S.No.	Product	Make	Specification	Qty	Rate (Rs.)
1.	Transformer	Kirloskar	1000 KVA	1	
2.	G.O. Switch	Havells	11KV Box type	2	
3.	Copper Earthing *			9	
4.	Cable Box HT Line *			4	
5.	Labour & Fitting Charges of transformer & cables				
6.	PVC Tape, Johnson Tape, Hardware, Clump, Gitti& Other Accessory			LM	
7.	Thimble Ring type		120 mm	100	
8.	Thimble Ring type		150 mm	70	
9.	Cable	Havells	120 mm 3.5 core Alu unarmed	300 Mtr.	
10.		KEI /	120 mm 3.5 core Alu unarmed	300 Mtr.	
11.		Poly Cab	120 mm 3.5 core Alu unarmed	300 Mtr.	
12.	Cable	Havells	150 mm 3.5 core Alu unarmed	1300 Mtr.	
13.		KEI	150 mm 3.5 core Alu unarmed	1300 Mtr.	
14.		Poly Cab	150 mm 3.5 core Alu unarmed	1300 Mtr.	
15.	Cabling (Labour Charges)		120 mm	300 Mtr.	
16.	Cabling (Labour Charges)		150 mm	1300 Mtr.	

- The above specification/ brand can be changed as per requirement or valid suggestion of vendor
- * Indicates items if required

DETAIL OF ITEMS Installation of Transformer & upgrading of Electricity load with cable & panels etc.

S.No.	Product	Make	Specification	Qty	Rate (Rs.)
1.	Panel Enclosure Fabricated with CRCA sheet 16 Gauge& 18 Gauge/Swg. Sheet Powder Coated with Siemens Gray Colour Indoor type Front Operation			1	
2.	Colour Corded Aluminium (Enercon) Bus Bar		300A Current Density 1.0 with Heat Shrinkable Sleeves	1	
3.	Bus Bar Supporter			1	
4.	Multifunction Meter (Nippen)	L & T / HPL		1	
5.	CT Coil (Nippen)	L & T	300 A/5A	3	
6.	Wire & Thimble, Tie Belt			LM	
7.	Indicator			3	
8.	MCB Channel & PVC Channel	L & T / HAVELLS		LM	
9.	Control MCB SP	L & T / HAVELLS	6A	3	
10.	Panel Lock Hardware, Ferrule & Spiral				
11.	TP MCCB with spreader Link & Rotary Handle	L & T	250A	1	
12.	MCB SP	L & T	6A -32A	45	
13.	Labour & Fitting Charges				

- The above specification/ brand can be changed as per requirement or valid suggestion of vendor
- * Indicates items if required