


SEALED TENDERS/ QUOTATIONS (WITH MATERIAL & LABOUR or MATERIAL / LABOUR SEPARATELY) ARE INVITED FOR

1. VARIOUS MATERIAL required like Cable, Panels, switches etc. with 1000 KVA DRY Transformer of Kirloskar Company (STAR LB, DELTA HT.) (Transformer & VCB Switch already ordered).
2. The installation of Cables & panels will be inside the building premises after Upgrading of Electricity load as per requirement of Montgomery Guru Nanak Public School, Adarsh Nagar, Jalandhar with in 7 working days.

For detail please visit School Website mgnadarshnagar.org and School premises for proper estimates and visit School to meet technical expert and undersigned.

Principal



DETAIL OF ITEMS FOR Installation of 1000 KVA Transformer & upgrading of Electricity load with cable & panels etc.

S. No.	Product			Make	Specification	Qty	Rate (Rs.)
1.	Copper Earthing *					9	
2.	Cable Box HT Line *					4	
3.	Labour & Fitting Charges of transformer & cables						
4.	PVC Tape, Johnson Tape, Hardware, Clump, Gitti & Other Accessory					LM	
5.	Thimble Ring type				120 mm	100	
6.	Thimble Ring type				150 mm	70	
7.	Cable			Havells	120 mm 3.5 core Alu Armoured	300 Mtr.	
8.				KEI /	120 mm 3.5 core Alu Armoured	300 Mtr.	
9.				Poly Cab	120 mm 3.5 core Alu Armoured	300 Mtr.	
10.	Cable			Havells	150 mm 3.5 core Alu Armoured	1300 Mtr.	
11.				KEI	150 mm 3.5 core Alu Armoured	1300 Mtr.	
12.				Poly Cab	150 mm 3.5 core Alu Armoured	1300 Mtr.	
13.	Cabling (Labour Charges)				120 mm	300 Mtr.	
14.	Cabling (Labour Charges)				150 mm	1300 Mtr.	

- The above specification/ brand can be changed as per requirement or valid suggestion of vendor
- * Indicates items if required

DETAIL OF ITEMS Installation of Transformer & upgrading of Electricity load with cable & panels etc.

S.No.	Product			Make	Specification	Qty	Rate (Rs.)
1.	Panel Enclosure Fabricated with CRCA sheet 16 Gauge & 18 Gauge /Swg. Sheet Powder Coated with Siemens Gray Colour Indoor type Front Operation					1	
2.	Colour Corded Aluminium (Enercon) Bus Bar				300A Current Density 1.0 with Heat Shrinkable Sleeves	1	
3.	Bus Bar Supporter					1	
4.	Multifunction Meter (Nippen)			L & T / HPL		1	
5.	CT Coil (Nippen)			L & T	300 A /5A	3	
6.	Wire & Thimble, Tie Belt					LM	
7.	Indicator					3	
8.	MCB Channel & PVC Channel			L & T / HAVELLS		LM	
9.	Control MCB SP			L & T / HAVELLS	6A	3	
10.	Panel Lock Hardware, Ferrule & Spiral						
11.	TP MCCB with spreader Link & Rotary Handle			L & T	250A	1	
12.	MCB SP			L & T	6A - 32A	45	
13.	Labour & Fitting Charges						

- The above specification/ brand can be changed as per requirement or valid suggestion of vendor
- * Indicates items if required